## Test Report No 151124-034301-F

Standby Power Measurement

Name: Address: Manufacturer: Description: Model: Serial Number: Rated Voltage: Rated Frequency: Documentation ref: Configuration:	Customer goughlui.com Testing 1 RoadTest Ave RoadTestVille RoadTestState 1234 RoadTestNation Unit Under Test OSRAM Lightify 9.5W Tunable White LED Globe	Name: Address: Date of issue: Manufacturer: Description: Model: Serial Number: Firmware Version: Test Software:	Reference Instrument Tektronix Power Analyzer PA1000 B010272 Ver.1.3.15
Time of Test: Test Voltage: Test Frequency: Voltage Distortion: Voltage Crest Factor: Temperature: Humidity:		Average Power: Power Limit: Power Stability: Uncertainty*: Test Period: Test Method: Test Status:	22.991 mW 00:15:00

Power measurements were carried out in accordance with the requirements of IEC 62301 Ed. 2 "Measurement of standby power" and EN 50564:2011 "Electrical and electronic household and office equipment - Measurement of low power consumption" in the laboratory environment, using equipment traceable to national or international standards. All testing was performed under computer control.

\* Uncertainty quoted is an avearge of power measurement uncertainties from the last 2/3 of the test which are due only to the accuracy of the reference instrument used. If Uncertainty is marked as FAIL it means that at least one power measurement uncertainty in the last 2/3 of the test exceeded the limit prescribed in the standard.

Test Notes

<none>

Test Officer Full Name: Gough Lui

Signature: \_\_\_\_\_

## goughlui.com

		T(C)	uits			
All values in this table refer to results from the last 2/3 of the test	Average	Minimum	Maximum	Min.Limit	Max.Limit	Status
Power	566.99 mW	551.59 mW	579.29 mW	N/A	1.0000 W	PASS
Voltage	231.43 V	231.38 V	231.50 V	227.70 V	232.30 V	PASS
Current	12.599 mA	12.259 mA	12.874 mA	N/A	N/A	N/A
Frequency	50.056 Hz	50.054 Hz	50.057 Hz	49.500 Hz	50.500 Hz	PASS
Power Factor	194.47 m	189.87 m	199.65 m	N/A	N/A	N/A
Voltage Crest Factor	1.4502	1.4491	1.4518	1.3400	1.4900	PASS
Current Crest Factor	11.205	9.6886	12.132	N/A	N/A	N/A
Voltage THC	561.65 m%	549.46 m%	572.31 m%	N/A	2.0000 %	PASS
Uncertainty Ratio*	2.3726	2.0525	2.5651	1.0000	N/A	PASS
Result Interval	N/A	N/A	0.5040 s	N/A	1.0000 s	PASS

## Results

\* Uncertainty Ratio is the ratio of 'Ulim/Ures', where 'Ures' is the uncertainty of each power measurement, due only to the accuracy of the reference instrument used.

Ullim' is the absolute allowed uncertainty, calculated for each power measurement in accordance with IEC63201 Ed.2 / EN 50564:2011 standards. If Uncertainty Ratio is marked as FAIL it means that at least one power measurement uncertainty in the last 2/3 of the test exceeded the limit prescribed in the standard.

